

## **Particle Physics Division Mechanical Department Engineering Note**

Number:

MD-ENG-094

Date: 12-12-05

Project Internal Reference: None.

Project:

Portable Air Compressor Engineering Note

Title:

FESHM 5031 Engineering Note

Author(s): Dave Pushka

Reviewer(s):Bob Wands

Key Words: Engineering note, silver sticker, pressure vessel

Abstract Summary: Engineering note for a code stamped pressure vessel used as an air receiver on a portable electrically powered air compressor assigned to the Mechanical Department Detector Installation group.

Applicable Codes: ASME Section VIII Division 1

# PRESSURE VESSEL ENGINERING NOTE PER CHAPTER 5031

Prepared by: <u>Dave Pushka</u> Preparation date: <u>08 December 2005</u>

Description and Identification Fill in the label information below: This vessel conforms to Fermilab ES&H Manual Chapter 5031 Vessel Title: EMGLO Portable air compressor PPD - 10098 Vessel Number ←Obtain from Division/Section Safety Officer Vessel Drawing Number: No drawing (commercial tank) Maximum Allowable Working Pressures (MAWP): Internal Pressure 240 psig External Pressure One atmosphere, 0 psig Working Temperature Range: -20 \_\_\_\_°F, 200 Contents: Compressed Air Designer/Manufacturer \_\_ LEISS MFG. INC. Test Pressure (if tested at Fermi) Acceptance ←Document per Chapter 5034 Not tested at Fermilab Date: \_\_\_ of the Fermilab ES&H Manual <u>n/a</u> PSI**G**, Hydraulic \_\_\_\_ Pneumatic\_ Accepted as conforming to standard by of Division/Section\_\_\_\_\_ Date:\_\_\_ ←Actual signature required NOTE: Any subsequent changes in contents, pressures, temperatures, valving, etc., which affect the safety of this vessel shall require another review. Reviewed by: Director's signature (or designee) if the vessel is for manned areas but doesn't conform to the requirements of the chapter. \_Date: \_

Lab Property Number(s): No Property Code Assigned
Lab Location Code: Lab E & F or where needed(obtain from safety officer)
Purpose of Vessel(s): Air Receiver for a portable air compressor
Vessel Capacity/Size: 15 gallons _ Diameter: 11 ½ inch _ Length: 33 inches
Normal Operating Pressure (OP) 125 psig
MAWP-OP = 115PSI
List the numbers of all pertinent drawings and the location of the originals.
Drawing # Location of Original
None Not applicable

#### 2. <u>Design Verification</u>

Is this vessel designed and built to meet the Code or "In-House Built" requirements? Yes\_X\_ No\_\_\_\_.

If "No" state the standard that was used \_\_\_\_\_.


Demonstrate that design calculations of that standard have been made and that other requirements of that standard have been satisfied.

Skip to part 3 "system venting verification."

Does the vessel(s) have a U stamp? Yes\_X\_ No\_\_\_. If "Yes", complete section 2A; if "No", complete section 2B.

A. Staple photo of U stamp plate below. Copy "U" label details to the side

Copy data here:



Certified by LEISS MFG INC

UM MAWP 240 psi @ 550 F

MDMT -20 F @ 240 psi

SN 141

2005

CRN H1765 56521

014

Provide ASME design calculations in an appendix. On the sketch below, circle all applicable sections of the ASME code per Section VIII, Division I. (Only for non-coded vessels)




Figure 1. ASME Code: Applicable Sections

2B.

### Summary of ASME Code

<u>Item</u>	Reference ASME Code Section	<pre>CALCULATION RESULT (Required thickness or stress level vs. actual thickness calculated stress level)</pre>		
		vs		
		vs		
		vs		
1		vs		
		vs		

3.	System Venting Verific	cation Pr	rovide the vent	t system schem	atic.	
	Does the venting system follow the Code UG-125 through UG-137? Yes_X_ No					
	Does the venting system also follow the Compressed Gas Association Standards S-1.1 and S-1.3? YesX_ No					
	A "no" response to both of the two proceeding questions requires a justification and statement regarding what standards were applied to verify system venting is adequate.					
	List of reliefs and se	ettings:				
	Manufacturer	Model #	Set Pressure	Flow Rate	Size	
	CDI of St. Louis MO	ST 25	200 PSIG	178 SCFM	¼ inch	MNPT
4.	Operating Procedure  Is an operating procedure vessel?  Yes NoX				of this	
5.	Welding Information					
	Has the vessel been fabricated in a non-code shop? Yes NoX If "Yes", append a copy of the welding shop statement of welder qualification (Procedure Qualification Record, PQR) which references the Welding Procedure Specification (WPS) used to weld this vessel.					
6.	Existing, Used and Uni	manned Are	ea Vessels			
	Is this vessel or any part thereof in the above categories? Yes NoX					
	If "Yes", follow the : Existing, Used and Uni			ended Engineer	ing Note	for
7.	Exceptional Vessels					
	Is this vessel or any Yes NoX	part the	reof in the abo	ove category?		
	If "Yes", follow the Exceptional Vessels.	requiremen	nts for an Exte	ended Engineer	ing Note	for

THIS VESSEL CONFORMS TO FERMILAB ES&H MANUAL CHAPTER 5031				
Vessel Title: Portable Air Compressor Air Receiver				
Vessel Number				
Vessel Drawing Number: Not applicable as this is a purchased commercial air receiver				
Maximum Allowable Working Pressures (MAWP):				
Internal Pressure: 240 psi at 550 F	*			
External Pressure: One atmosphere (0 psig)				
Working Temperature Range -20 °F to 550 °F				
Contents: Compressed Air				
Designer: LEISS Manufacturing Inc.				
Test Pressure (if tested at Fermi) Not tested at FNAL DATE/				
PSIG, HydraulicPneumatic				
Accepted as conforming to standard by				
Of Division/Section				
NOTE: Any subsequent changes in content, pressures, temperatures, valving, etc., which affect the vessel shall require another review and test.	safety of this			

Figure 2. Sample of sticker to be completed and be placed on vessel.

#### RELIEF VALVE SIZING CRITERIA:

Compressor is an EMGLO Pump model LU. The currently produced version of this pump is a Model G pump according to a representative of EMGLO. Displacement of the model LU and model G pumps is 13.8 cfm.

The compressor is fitted with a General Air Products (1-800-345-8207) Model 69MC8LY pressure switch. This switch includes an unloader valve. The unloader valve stops the compressor intake valves from opening at 125 psig (pump continues to rotate but no air is compressed – this is to limit the on-off cycling of the compressor motor). The pressure switch shuts off the motor at 150 psig. The relief valve is set at 200 psig and the maximum allowable working pressure of the air receiver is 240 psig.

The compressor is the sole source of pressure for the receiver. The vessel if used indoors is in areas with fire protection, so a fire condition is not a credible source of pressure. Therefore, the relief valve capacity is only dependent on the compressor displacement.

The compressor displacement is 13.8 cfm. The relief valve capacity is 178 cfm at 220 psig (110% of the set pressure). Therefore, the relief valve capacity exceeds the compressor capacity and this meets the ASME requirements.

Relief valve was purchased new in December 2005 and installed at that time. The relief valve will need to be re-tested or replaced in 2011. Cost of the Relief valve was \$6.38 from Granger.

Fermilab ES&H Manual

5031TA-6 Rev. 12/2000